



Galaxy S25 Ultra



Galaxy S25 Ultra



Galaxy S25 Ultra



Galaxy S25 Ultra



Galaxy S25 Ultra



Galaxy S25 Ultra



Galaxy S25 Ultra



Galaxy S25 Ultra



Galaxy S25 Ultra



Galaxy S25 Ultra



Galaxy S25 Ultra



Galaxy S25 Ultra



Galaxy S25 Ultra



Galaxy S25 Ultra



Galaxy S25 Ultra

























































MAX
THERMASHEATH
CONTINUOUS INSULATION
Optimum Energy Efficiency

- Excellent resistance to water and vapor
- Air Barrier
- Use with Maxx 6-SEAL Construction Tape or R-SEAL 3000 to seal joints.

Thickness	R-Value
1/2"	0.5
5/8"	0.7
1"	1.0
1 1/2"	1.5
2"	2.0
2 1/2"	2.5
3"	3.0
3 1/2"	3.5
4"	4.0
4 1/2"	4.5

Seal and Insulate
with ENERGY STAR



Maxx Thermal Systems, Inc.
P.O. Box 100
Houston, TX 77240
www.maxx.com

- Why choose Maxx Polyfoam water vapor resistant insulation?
- Excellent for performance
 - High moisture resistance (ASTM)
 - Excellent air barrier
 - Excellent for water vapor resistance
 - Excellent for air barrier
 - Excellent for water vapor resistance


MAX
THERMASHEATH
CONTINUOUS INSULATION
Optimum Energy Efficiency



Maxx Thermal Systems, Inc.
P.O. Box 100
Houston, TX 77240
www.maxx.com









THERMASHEATH®

CONTINUOUS INSULATION
Optimizing Energy Efficiency

*Chronicles
For now have
Chosen And sa
this house, that m
Name may be there
Ever! and mine eyes
and mine heart shall
Perpetually.*

PROPERTIES

Thickness (in.)	R-Value
3/8	3.2
1/2	4.0
5/8	5.0
3/4	6.0
7/8	7.8
1	9.6
1 1/8	10.0
1 1/4	13.1
1 1/2	16.7
1 3/4	20.3
2	23.9
2 1/2	27.4
3	31.0



Rmax Thermasheath is an energy efficient insulation board composed of closed cell polyisocyanurate (polyiso) foam reinforced aluminum foil facers on each side.

COMPLIANCES:

- International Building Code (IBC)
- International Residential Code (IRC)
- International Energy Conservation Code (IECC)
- ASHRAE 90.1

Refer to the product data sheet for compliance, physical properties and other information. For warranties, limitations and recommendations, consult your local building codes.

NOTE:

This product is not a structural component. It is not to be used as a nailing base for any other building materials.

WARNING:

POLYISO foam is a flammable material. It must be properly sealed for lateral loads and fire spread. Consult your local building codes for the use of a thermal or ignition barrier.

Consult the Rmax website for more information. For details regarding suitable applications, additional recommendations, for warranties, limitations and recommendations, consult your local building codes.

NOTA: Este producto no es un componente estructural. No debe ser utilizado como una base de clavado para otros materiales de construcción.

ADVERTENCIA: espuma POLYISO es un material inflamable. Debe estar sellado correctamente para la propagación de las llamas. Consulte el folleto de instrucciones para los códigos y requisitos de construcción.

- Date County Product Control Approval
- California Code of Regulations, Title 24
- Du TER 1207-01 & 1209-03
- Tested to acceptance criteria of ICC-ES

For details regarding suitable applications, additional recommendations, for warranties, limitations and recommendations, consult your local building codes.

Why choose Rmax Polyiso over other products?

- Excellent for exterior applications
- High service temperature (220°F)
- Energy efficient high R-value per inch
- Excellent resistance to moisture and mold
- Air Barrier
- Use with Rmax W-2 All Climate Guard
- 8 SFAL 9300 to seal joints



CONTINUOUS INSULATION
Optimizing Energy Efficiency

Thickness (in.)	R-Value
3/8	3.2
1/2	4.0
5/8	5.0
3/4	6.0
7/8	7.8
1	9.6
1 1/8	10.0
1 1/4	13.1
1 1/2	16.7
1 3/4	20.3
2	23.9
2 1/2	27.4
3	31.0



Rmax Thermasheath is an energy efficient insulation board composed of closed cell polyisocyanurate (polyiso) foam reinforced aluminum foil facers on each side.

COMPLIANCES:

- International Building Code (IBC)
- International Residential Code (IRC)
- International Energy Conservation Code (IECC)
- ASHRAE 90.1

Refer to the product data sheet for compliance, physical properties and other information. For warranties, limitations and recommendations, consult your local building codes.

NOTE:

This product is not a structural component. It is not to be used as a nailing base for any other building materials.

WARNING:

POLYISO foam is a flammable material. It must be properly sealed for lateral loads and fire spread. Consult your local building codes for the use of a thermal or ignition barrier.

Consult the Rmax website for more information. For details regarding suitable applications, additional recommendations, for warranties, limitations and recommendations, consult your local building codes.

NOTA: Este producto no es un componente estructural. No debe ser utilizado como una base de clavado para otros materiales de construcción.

ADVERTENCIA: espuma POLYISO es un material inflamable. Debe estar sellado correctamente para la propagación de las llamas. Consulte el folleto de instrucciones para los códigos y requisitos de construcción.


- Excellent for exterior applications
- High service temperature (220°F)
- Energy efficient high R-value per inch
- Excellent resistance to moisture and mold
- Air Barrier
- Use with Rmax W-2 All Climate Guard
- 8 SFAL 9300 to seal joints



LIST OF ABBREVIATIONS

AB	ANCHOR BOLT
ABV	ABOVE
AFF	ABOVE FINISHED FLOOR
ADJ	ADJACENT
AHU	AIR HANDLER UNIT
ALUM	ALUMINUM
BRG	BEARING
BLK	BLOCK
BOTT	BOTTOM
BLDG	BUILDING
B.O	BOTTOM OF
CLG	CEILING
CLR	CLEAR, CLEARANCE
COL	COLUMN
CONC	CONCRETE
CMU	CONCRETE MASONRY UNIT
CU	CONDENSER UNIT
CONST	CONSTRUCTION
CONT	CONTINUE, CONTINUOUS
CJ	CONTROL JOINT
DIAG	DIAGONAL
DIA	DIAMETER
DIM	DIMENSION
DN	DOWN
DS	DOWNSPOUT
DWG	DRAWING
DW	DISHWASHER
EA	EACH
EW	EACH WAY
ELEC	ELECTRIC
EWIC	ELECTRIC WATER COOLER
ELEV	ELEVATION (VERTICAL HEIGHT)
EQ	EQUAL
EXH	EXHAUST
EJ	EXPANSION JOINT
EXT	EXTERIOR
FA	FIRE ALARM
FE	FIRE EXTINGUISHER
FIXT	FIXTURE
FD	FLOOR DRAIN
FTG	FOOTING
FUR	FURRED
FT	FOOT
GA	GAGE, GAUGE
GALV	GALVANIZED
GFI	GROUND FAULT INTERRUPTER
GYP BD	GYPSUM WALLBOARD
HDR	HEADER
HVAC	HEATING/VENTILATING/AIR CONDITIONING
HT	HEIGHT
HC	HOLLOW CORE
HORZ	HORIZONTAL
HB	HOSE BIBS
HM	HOLLOW METAL
INCL	INCLUDE, (ED), (ING)
ID	INSIDE DIAMETER
INSUL	INSULATE, (ED), (ING)
INT	INTERIOR
IN	INCH
JT	JOINT
LAV	LAVATORY
LT	LIGHT
LW	LIGHTWEIGHT
LLH	LONG LEG HORIZONTAL
LLV	LONG LEG VERTICAL
MAX	MAXIMUM
MET	METAL
MW	MICROWAVE
MIN	MINIMUM
MISC	MISCELLANEOUS
MO	MASONRY OPENING
N/A	NOT APPLICABLE
NOM	NOMINAL
NTS	NOT TO SCALE
OC	ON CENTER
OPNG	OPENING
OD	OUTSIDE DIAMETER
OHD	OVERHEAD
OPP	OPPOSITE
PLWD	PLYWOOD
PSF	PRESSURE TREATED
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PREFAB	PREFABRICATE, (ED)
PFN	PREFINISHED
QT	QUARRY TILE
RAD	RADIUS
REC	RECESS, (ED)
REF	REFRIGERATOR
REINF	REINFORCE, (ED), (ING)
REQD	REQUIRED
RA	RETURN AIR
R/S	ROD AND SHELF
RD	ROOF DRAIN
RO	ROUGH OPENING
SCH	SCHEDULE
SECT	SECTION
SHT	SHEET
SH	SINGLE HUNG
SIM	SIMILAR
SC	SOLID CORE
SGD	SLIDING GLASS DOOR
SPK	SPEAKER
SPEC	SPECIFICATION
SQ	SQUARE
STD	STANDARD
STO	STORAGE
STR	STRUCTURAL
SYS	SYSTEM
TEL	TELEPHONE
TEMP	TEMPERED
TV	TELEVISION
THK	THICK, (NESS)
T&G	TONGUE AND GROOVE
TYP	TYPICAL
T.O	TOP OF
UNO	UNLESS NOTED OTHERWISE
VB	VAPOR BARRIER
VERT	VERTICAL
VCT	VINYL COMPOSITION TILE
VP	VAPOR PROOF
VTR	VENT THROUGH ROOF
WH	WATER HEATER
WC	WATER CLOSET
WP	WATERPROOFING
WR	WATER RESISTANT
WWF	WELDED WIRE FABRIC
W	WITH
W/O	WITHOUT
WD	WOOD

SYMBOL LEGEND



MODEL SAPPHIRE

STRUCTURAL NOTES

GENERAL:

- ALL WORK TO BE IN STRICT ACCORDANCE WITH FLORIDA BUILDING CODE RESIDENTIAL 2023, 8th EDITION AND ASCE 7-22.
- DO NOT SCALE DRAWINGS, USE WRITTEN DIMENSIONS FOR ALL MEASUREMENTS. ALL DIMENSIONS ARE FACE OF STUD OR FACE OF CMU.

CONCRETE:

- ALL WORK TO BE IN STRICT ACCORDANCE WITH ACI 318.
- MIX DESIGN CRITERIA: REFER TO THE SPECIFICATIONS. ALL CONCRETE TYPE I PORTLAND CEMENT (ASTM C150) 3,000 PSI COMPRESSIVE STRENGTH @28 DAYS. (U.O.N) W/C RATIO LESS OR EQUAL TO 0.58 SLUMP - SLAB ON GRADE: 5" WATER: POTABLE CHLORIDE: NONE

FOUNDATIONS:

- FOOTING DESIGN BASED ON A MINIMUM ALLOWABLE SOIL BEARING PRESSURE OF 2,500 PSF.
- CAUTION SHALL BE USED WHEN OPERATING VIBRATORY COMPACTION EQUIPMENT NEAR EXISTING STRUCTURES TO AVOID RISK OF DAMAGING THE EXISTING STRUCTURE.
- IF FOOTING ELEVATION OCCURS IN DISTURBED, UNSTABLE OR UNSUITABLE SOIL, THE ENGINEER SHALL BE NOTIFIED AND NECESSARY ADJUSTMENTS SHALL BE MADE PER HIS INSTRUCTIONS.
- TERMITE PROTECTION SHALL BE PROVIDED BY REGISTERED TERMITICIDES. TERMITE PROTECTION SHALL BE PROVIDED BY REGISTERED TERMITICIDES, INCLUDING SOIL APPLIED PESTICIDES, BAITING SYSTEMS AND PESTICIDES APPLIED TO WOOD, UPON COMPLETION OF THE TERMITE PROTECTION TREATMENT, A CERTIFICATE OF COMPLIANCE SHALL BE ISSUED TO THE BUILDING DEPARTMENT BY THE LICENSED PEST CONTROL COMPANY THAT CONTAINS THE FOLLOWING STATEMENT: "THE BUILDING HAS RECEIVED A COMPLETE TREATMENT FOR THE PREVENTION OF SUBTERRANEAN TERMITES. TREATMENT IS IN ACCORDANCE WITH THE RULES AND LAWS ESTABLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTURE AND CONSUMER SERVICES. (FBC-R318.1)

MASONRY:

- DESIGN, MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE ACI DESIGN, MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE ACI STANDARD BUILDING CODE REQUIREMENTS FOR CONCRETE MASONRY STRUCTURES: ACI 530/ACI 530.1.
- CMU CELLS INDICATED IN PLAN OR NOTES AS FILLED CELLS SHALL BE GROUTED WITH 3,000 PSI CONCRETE. (8" TO 10" SLUMP)
- CMU CONCRETE BLOCKS SHALL CONFORM TO ASTM C-90 (28 DAY STRENGTH 2,000 PSI) (F'm=1,500 PSI), LAID IN RUNNING BOND.
- MORTAR SHALL BE TYPE S OR M.
- PROVIDE VERTICAL REINFORCING IN CMU WALLS AS SHOWN IN PLANS.
- ROVIDE HORIZONTAL JOINT REINFORCING AT 24" O.C. VERTICAL IN CMU WALLS.
- ALL REINFORCING STEEL SHALL CONFORM WITH ASTM A615, GRADE 60.

WOOD:

- FOR STRUCTURAL LUMBER, PROVIDE THE FOLLOWING GRADE AND SPECIES (OR EQUIVALENT): SOUTHERN PINE GRADE #2 DENSE W/ Fb=1,300 PSI MIN.
- ALL WOOD IN CONTACT WITH GROUND, EMBEDDED IN CONCRETE IN DIRECT CONTACT ALL WOOD IN CONTACT WITH GROUND, EMBEDDED IN CONCRETE IN DIRECT CONTACT WITH THE GROUND OR EMBEDDED IN CONCRETE EXPOSED TO THE WEATHER THAT SUPPORTS PERMANENT STRUCTURES INTENDED FOR HUMAN OCCUPANCY SHALL BE APPROVED PRESSURE PRESERVATIVE TREATED WOOD SUITABLE FOR GROUND CONTACT USE.
- WOOD TRUSSES SHALL BE SIZED AND DETAILED TO FIT THE DIMENSIONS AND LOADS. PERMANENT BRIDGING PERPENDICULAR TO THE SPAN OF THE TRUSS SHALL BE PROVIDED AS REQUIRED BY TRUSS MANUFACTURER.
- PROVIDE GALVANIZED METAL HANGERS AND FRAMING ANCHORS OF THE SIZE AND TYPE RECOMMENDED BY TRUSS MANUFACTURER (SIMPSON STRONG TIE OR EQUIVALENT)
- PROVIDE HURRICANE CLIPS OR ANCHORS AT ALL CONNECTIONS.
- ALL BOLTS USED FOR CONSTRUCTION SHALL BE ~" MIN. (ASTM A-370), 12"~ MIN. (ASTM A-370).

VERIFICATION OF FIELD CONDITIONS:

CONTRACTOR SHALL VERIFY ALL FIELD CONDITIONS AND DIMENSIONS RELATIVE TO SAME. WHERE THERE ARE CONFLICTS BETWEEN ACTUAL FIELD CONDITIONS AND DATA PRESENTED IN THE DRAWINGS, SUCH CONDITIONS SHALL BE CALLED TO THE ENGINEER'S ATTENTION AND NECESSARY ADJUSTMENTS MADE PER HIS INSTRUCTIONS.

DESIGN PARAMETERS

APPLICABLE CODES:
2023 FLORIDA BUILDING CODE (8TH EDITION)
2023 FLORIDA BUILDING CODE RESIDENTIAL (8TH EDITION)
2023 (ACCESSIBILITY)
2023 (ENERGY CONSERVATION)
2023 (EXISTING BUILDING)
2023 (FUEL GAS)
2023 (MECHANICAL)
2023 (PLUMBING)
2023 (ELECTRICAL)
CHAPTER FAC 60A-60 OF THE FLORIDA FIRE PREVENTION CODE, 8th EDITION

METHOD OF DESIGN:
DESIGNED PURSUANT TO RESIDENTIAL FLORIDA BUILDING CODES 2023-8th EDITION
CHAPTER 16 & 20, AA-ASIA-38 SPECIFICATIONS FOR ALUMINUM STRUCTURES, & ASCE 7-10 MINIMUM DESIGN LOAD, & ASCE 7-16, SECTION 26.2 BUILDING PARTIALLY (IF APPLICABLE) & CHAPTER 32 OF ASCE-7 SECTION 1603.1.4 (TORNADO LOADS)





BASIC WIND SPEED:
☐ 170 MPH (ULTIMATE DESIGN 3 SECOND GUST) = 132 MPH NOMINAL DESIGN(FATEST MILE)
☐ 160 MPH (ULTIMATE DESIGN 3 SECOND GUST) = 124 MPH NOMINAL DESIGN(FATEST MILE)
☐ 150 MPH (ULTIMATE DESIGN 3 SECOND GUST) = 116 MPH NOMINAL DESIGN(FATEST MILE)
☒ 140 MPH (ULTIMATE DESIGN 3 SECOND GUST) = 110 MPH NOMINAL DESIGN(FATEST MILE)

RISK CATEGORY:
☒ 1
☐ 2
☐ 3
☐ 4

BUILDING OCCUPANCY CLASSIFICATION:

☐ GROUP A - ASSEMBLY
☐ GROUP B - BUSINESS
☐ GROUP C - COMMERCIAL
☐ GROUP D - DAY CARE CENTER
☐ GROUP E - EDUCATIONAL
☐ GROUP F -FACTORY INDUSTRIAL
☐ GROUP H - HAZARDOUS
☐ GROUP I - INSTITUTIONAL
☐ GROUP M - MERCANTILE
☒ GROUP R - RESIDENTIAL
☐ GROUP S - STORAGE


BUILDING OCCUPANCY CLASSIFICATION:
☐ TYPE I-A
☐ TYPE I-B
☐ TYPE II-A
☐ TYPE II-B
☐ TYPE II-C
☐ TYPE II-D
☐ TYPE II-E
☐ TYPE II-F
☐ TYPE II-G
☐ TYPE II-H
☐ TYPE II-I
☐ TYPE II-J
☐ TYPE II-K
☐ TYPE II-L
☐ TYPE II-M
☐ TYPE II-N
☐ TYPE II-O
☐ TYPE II-P
☐ TYPE II-Q
☐ TYPE II-R
☐ TYPE II-S
☐ TYPE II-T
☐ TYPE II-U
☐ TYPE II-V
☐ TYPE II-W
☐ TYPE II-X
☐ TYPE II-Y
☐ TYPE II-Z
☐ TYPE II-AA
☐ TYPE II-AB
☐ TYPE II-AC
☐ TYPE II-AD
☐ TYPE II-AE
☐ TYPE II-AF
☐ TYPE II-AG
☐ TYPE II-AH
☐ TYPE II-AI
☐ TYPE II-AJ
☐ TYPE II-AL
☐ TYPE II-AM
☐ TYPE II-AN
☐ TYPE II-AO
☐ TYPE II-AP
☐ TYPE II-AQ
☐ TYPE II-AR
☐ TYPE II-AS
☐ TYPE II-AT
☐ TYPE II-AU
☐ TYPE II-AV
☐ TYPE II-AW
☐ TYPE II-AX
☐ TYPE II-AY
☐ TYPE II-AZ
☐ TYPE II-BA
☐ TYPE II-BB
☐ TYPE II-BC
☐ TYPE II-BD
☐ TYPE II-BE
☐ TYPE II-BF
☐ TYPE II-BG
☐ TYPE II-BH
☐ TYPE II-BI
☐ TYPE II-BJ
☐ TYPE II-BL
☐ TYPE II-BM
☐ TYPE II-BN
☐ TYPE II-BO
☐ TYPE II-BP
☐ TYPE II-BQ
☐ TYPE II-BR
☐ TYPE II-BS
☐ TYPE II-BT
☐ TYPE II-BU
☐ TYPE II-BV
☐ TYPE II-BW
☐ TYPE II-BX
☐ TYPE II-BY
☐ TYPE II-BZ
☐ TYPE II-CA
☐ TYPE II-CB
☐ TYPE II-CC
☐ TYPE II-CD
☐ TYPE II-CE
☐ TYPE II-CF
☐ TYPE II-CG
☐ TYPE II-CH
☐ TYPE II-CI
☐ TYPE II-CJ
☐ TYPE II-CL
☐ TYPE II-CM
☐ TYPE II-CN
☐ TYPE II-CO
☐ TYPE II-CP
☐ TYPE II-CQ
☐ TYPE II-CR
☐ TYPE II-CS
☐ TYPE II-CT
☐ TYPE II-CU
☐ TYPE II-CV
☐ TYPE II-CW
☐ TYPE II-CX
☐ TYPE II-CY
☐ TYPE II-CZ
☐ TYPE II-DA
☐ TYPE II-DB
☐ TYPE II-DC
☐ TYPE II-DD
☐ TYPE II-DE
☐ TYPE II-DF
☐ TYPE II-DG
☐ TYPE II-DH
☐ TYPE II-DI
☐ TYPE II-DJ
☐ TYPE II-DL
☐ TYPE II-DM
☐ TYPE II-DN
☐ TYPE II-DO
☐ TYPE II-DP
☐ TYPE II-DQ
☐ TYPE II-DR
☐ TYPE II-DS
☐ TYPE II-DT
☐ TYPE II-DU
☐ TYPE II-DV
☐ TYPE II-DW
☐ TYPE II-DX
☐ TYPE II-DY
☐ TYPE II-DZ
☐ TYPE II-EA
☐ TYPE II-EB
☐ TYPE II-EC
☐ TYPE II-ED
☐ TYPE II-EE
☐ TYPE II-EF
☐ TYPE II-EG
☐ TYPE II-EH
☐ TYPE II-EI
☐ TYPE II-EJ
☐ TYPE II-EL
☐ TYPE II-EM
☐ TYPE II-EN
☐ TYPE II-EO
☐ TYPE II-EP
☐ TYPE II-EQ
☐ TYPE II-ER
☐ TYPE II-ES
☐ TYPE II-ET
☐ TYPE II-EU
☐ TYPE II-EV
☐ TYPE II-EW
☐ TYPE II-EX
☐ TYPE II-EY
☐ TYPE II-EZ
☐ TYPE II-FA
☐ TYPE II-FB
☐ TYPE II-FC
☐ TYPE II-FD
☐ TYPE II-FE
☐ TYPE II-FG
☐ TYPE II-FH
☐ TYPE II-FI
☐ TYPE II-FJ
☐ TYPE II-FL
☐ TYPE II-FM
☐ TYPE II-FN
☐ TYPE II-FO
☐ TYPE II-FP
☐ TYPE II-FQ
☐ TYPE II-FR
☐ TYPE II-FS
☐ TYPE II-FT
☐ TYPE II-FU
☐ TYPE II-FV
☐ TYPE II-FW
☐ TYPE II-FX
☐ TYPE II-FY
☐ TYPE II-FZ
☐ TYPE II-GA
☐ TYPE II-GB
☐ TYPE II-GC
☐ TYPE II-GD
☐ TYPE II-GE
☐ TYPE II-GF
☐ TYPE II-GG
☐ TYPE II-GH
☐ TYPE II-GI
☐ TYPE II-GJ
☐ TYPE II-GL
☐ TYPE II-GM
☐ TYPE II-GN
☐ TYPE II-GO
☐ TYPE II-GP
☐ TYPE II-GQ
☐ TYPE II-GR
☐ TYPE II-GS
☐ TYPE II-GT
☐ TYPE II-GU
☐ TYPE II-GV
☐ TYPE II-GW
☐ TYPE II-GX
☐ TYPE II-GY
☐ TYPE II-GZ
☐ TYPE II-HA
☐ TYPE II-HB
☐ TYPE II-HC
☐ TYPE II-HD
☐ TYPE II-HE
☐ TYPE II-HF
☐ TYPE II-HG
☐ TYPE II-HH
☐ TYPE II-HI
☐ TYPE II-HJ
☐ TYPE II-HL
☐ TYPE II-HM
☐ TYPE II-HN
☐ TYPE II-HO
☐ TYPE II-HP
☐ TYPE II-HQ
☐ TYPE II-HR
☐ TYPE II-HS
☐ TYPE II-HT
☐ TYPE II-HU
☐ TYPE II-HV
☐ TYPE II-HW
☐ TYPE II-HX
☐ TYPE II-HY
☐ TYPE II-HZ
☐ TYPE II-IA
☐ TYPE II-IB
☐ TYPE II-IC
☐ TYPE II-ID
☐ TYPE II-IE
☐ TYPE II-IF
☐ TYPE II-IG
☐ TYPE II-IH
☐ TYPE II-II
☐ TYPE II-IJ
☐ TYPE II-IL
☐ TYPE II-IM
☐ TYPE II-IN
☐ TYPE II-IO
☐ TYPE II-IP
☐ TYPE II-IQ
☐ TYPE II-IR
☐ TYPE II-IS
☐ TYPE II-IT
☐ TYPE II-IU
☐ TYPE II-IV
☐ TYPE II-IW
☐ TYPE II-IX
☐ TYPE II-IY
☐ TYPE II-IZ
☐ TYPE II-JA
☐ TYPE II-JB
☐ TYPE II-JC
☐ TYPE II-JD
☐ TYPE II-JE
☐ TYPE II-JF
☐ TYPE II-JG
☐ TYPE II-JH
☐ TYPE II-JI
☐ TYPE II-JJ
☐ TYPE II-JL
☐ TYPE II-JM
☐ TYPE II-JN
☐ TYPE II-JO
☐ TYPE II-JP
☐ TYPE II-JQ
☐ TYPE II-JR
☐ TYPE II-JS
☐ TYPE II-JT
☐ TYPE II-JU
☐ TYPE II-JV
☐ TYPE II-JW
☐ TYPE II-JX
☐ TYPE II-JY
☐ TYPE II-JZ
☐ TYPE II-KA
☐ TYPE II-KB
☐ TYPE II-KC
☐ TYPE II-KD
☐ TYPE II-KE
☐ TYPE II-KF
☐ TYPE II-KG
☐ TYPE II-KH
☐ TYPE II-KI
☐ TYPE II-KJ
☐ TYPE II-KL
☐ TYPE II-KM
☐ TYPE II-KN
☐ TYPE II-KO
☐ TYPE II-KP
☐ TYPE II-KQ
☐ TYPE II-KR
☐ TYPE II-KS
☐ TYPE II-KT
☐ TYPE II-KU
☐ TYPE II-KV
☐ TYPE II-KW
☐ TYPE II-KX
☐ TYPE II-KY
☐ TYPE II-KZ
☐ TYPE II-LA
☐ TYPE II-LB
☐ TYPE II-LC
☐ TYPE II-LD
☐ TYPE II-LE
☐ TYPE II-LF
☐ TYPE II-LG
☐ TYPE II-LH
☐ TYPE II-LI
☐ TYPE II-LJ
☐ TYPE II-LK
☐ TYPE II-LM
☐ TYPE II-LN
☐ TYPE II-LO
☐ TYPE II-LP
☐ TYPE II-LQ
☐ TYPE II-LR
☐ TYPE II-LS
☐ TYPE II-LT
☐ TYPE II-LU
☐ TYPE II-LV
☐ TYPE II-LW
☐ TYPE II-LX
☐ TYPE II-LY
☐ TYPE II-LZ
☐ TYPE II-MA
☐ TYPE II-MB
☐ TYPE II-MC
☐ TYPE II-MD
☐ TYPE II-ME
☐ TYPE II-MF
☐ TYPE II-MG
☐ TYPE II-MH
☐ TYPE II-MI
☐ TYPE II-MJ
☐ TYPE II-ML
☐ TYPE II-MN
☐ TYPE II-MO
☐ TYPE II-MP
☐ TYPE II-MQ
☐ TYPE II-MR
☐ TYPE II-MS
☐ TYPE II-MT
☐ TYPE II-MU
☐ TYPE II-MV
☐ TYPE II-MW
☐ TYPE II-MX
☐ TYPE II-MY
☐ TYPE II-MZ
☐ TYPE II-NA
☐ TYPE II-NB
☐ TYPE II-NC
☐ TYPE II-ND
☐ TYPE II-NE
☐ TYPE II-NF
☐ TYPE II-NG
☐ TYPE II-NH
☐ TYPE II-NI
☐ TYPE II-NJ
☐ TYPE II-NL
☐ TYPE II-NM
☐ TYPE II-NO
☐ TYPE II-NP
☐ TYPE II-NQ
☐ TYPE II-NR
☐ TYPE II-NS
☐ TYPE II-NT
☐ TYPE II-NU
☐ TYPE II-NV
☐ TYPE II-NW
☐ TYPE II-NX
☐ TYPE II-NY
☐ TYPE II-NZ
☐ TYPE II-OA
☐ TYPE II-OB
☐ TYPE II-OC
☐ TYPE II-OD
☐ TYPE II-OE
☐ TYPE II-OF
☐ TYPE II-OG
☐ TYPE II-OH
☐ TYPE II-OI
☐ TYPE II-OJ
☐ TYPE II-OL
☐ TYPE II-OM
☐ TYPE II-ON
☐ TYPE II-OO
☐ TYPE II-OP
☐ TYPE II-OQ
☐ TYPE II-OR
☐ TYPE II-OS
☐ TYPE II-OT
☐ TYPE II-OU
☐ TYPE II-OV
☐ TYPE II-OW
☐ TYPE II-OX
☐ TYPE II-OY
☐ TYPE II-OZ
☐ TYPE II-PA
☐ TYPE II-PB
☐ TYPE II-PC
☐ TYPE II-PD
☐ TYPE II-PE
☐ TYPE II-PF
☐ TYPE II-PG
☐ TYPE II-PH
☐ TYPE II-PI
☐ TYPE II-PJ
☐ TYPE II-PL
☐ TYPE II-PM
☐ TYPE II-PN
☐ TYPE II-PO
☐ TYPE II-PP
☐ TYPE II-PQ
☐ TYPE II-PR
☐ TYPE II-PS
☐ TYPE II-PT
☐ TYPE II-PU
☐ TYPE II-PV
☐ TYPE II-PW
☐ TYPE II-PX
☐ TYPE II-PY
☐ TYPE II-PZ
☐ TYPE II-QA
☐ TYPE II-QB
☐ TYPE II-QC
☐ TYPE II-QD
☐ TYPE II-QE
☐ TYPE II-QF
☐ TYPE II-QG
☐ TYPE II-QH
☐ TYPE II-QI
☐ TYPE II-QJ
☐ TYPE II-QL
☐ TYPE II-QM
☐ TYPE II-QN
☐ TYPE II-QO
☐ TYPE II-QP
☐ TYPE II-QQ
☐ TYPE II-QR
☐ TYPE II-QS
☐ TYPE II-QT
☐ TYPE II-QU
☐ TYPE II-QV
☐ TYPE II-QW
☐ TYPE II-QX
☐ TYPE II-QY
☐ TYPE II-QZ
☐ TYPE II-RA
☐ TYPE II-RB
☐ TYPE II-RC
☐ TYPE II-RD
☐ TYPE II-RE
☐ TYPE II-RF
☐ TYPE II-RG
☐ TYPE II-RH
☐ TYPE II-RI
☐ TYPE II-RJ
☐ TYPE II-RL
☐ TYPE II-RM
☐ TYPE II-RN
☐ TYPE II-RO
☐ TYPE II-RP
☐ TYPE II-RQ
☐ TYPE II-RR
☐ TYPE II-RS
☐ TYPE II-RT
☐ TYPE II-RU
☐ TYPE II-RV
☐ TYPE II-RW
☐ TYPE II-RX
☐ TYPE II-RY
☐ TYPE II-RZ
☐ TYPE II-SA
☐ TYPE II-SB
☐ TYPE II-SC
☐ TYPE II-SD
☐ TYPE II-SE
☐ TYPE II-SF
☐ TYPE II-SG
☐ TYPE II-SH
☐ TYPE II-SI
☐ TYPE II-SJ
☐ TYPE II-SL
☐ TYPE II-SM
☐ TYPE II-SN
☐ TYPE II-SO
☐ TYPE II-SP
☐ TYPE II-SQ
☐ TYPE II-SR
☐ TYPE II-SS
☐ TYPE II-ST
☐ TYPE II-SU
☐ TYPE II-SV
☐ TYPE II-SW
☐ TYPE II-SX
☐ TYPE II-SY
☐ TYPE II-SZ
☐ TYPE II-TA
☐ TYPE II-TB
☐ TYPE II-TC
☐ TYPE II-TD
☐ TYPE II-TE
☐ TYPE II-TF
☐ TYPE II-TG
☐ TYPE II-TH
☐ TYPE II-TI
☐ TYPE II-TJ
☐ TYPE II-TL
☐ TYPE II-TM
☐ TYPE II-TN
☐ TYPE II-TO
☐ TYPE II-TP
☐ TYPE II-TQ
☐ TYPE II-TR
☐ TYPE II-TS
☐ TYPE II-TT
☐ TYPE II-TU
☐ TYPE II-TV
☐ TYPE II-TW
☐ TYPE II-TX
☐ TYPE II-TY
☐ TYPE II-TZ
☐ TYPE II-UA
☐ TYPE II-UB
☐ TYPE II-UC
☐ TYPE II-UD
☐ TYPE II-UE
☐ TYPE II-UF
☐ TYPE II-UG
☐ TYPE II-UH
☐ TYPE II-UI
☐ TYPE II-UJ
☐ TYPE II-UL
☐ TYPE II-UM
☐ TYPE II-UN
☐ TYPE II-UO
☐ TYPE II-UP
☐ TYPE II-UQ
☐ TYPE II-UR
☐ TYPE II-US
☐ TYPE II-UT
☐ TYPE II-UV
☐ TYPE II-UW
☐ TYPE II-UX
☐ TYPE II-UY
☐ TYPE II-UZ
☐ TYPE II-VA
☐ TYPE II-VB
☐ TYPE II-VC
☐ TYPE II-VD
☐ TYPE II-VE
☐ TYPE II-VF
☐ TYPE II-VG
☐ TYPE II-VH
☐ TYPE II-VI
☐ TYPE II-VJ
☐ TYPE II-VL
☐ TYPE II-VM
☐ TYPE II-VN
☐ TYPE II-VO
☐ TYPE II-VP
☐ TYPE II-VQ
☐ TYPE II-VR
☐ TYPE II-VS
☐ TYPE II-VT
☐ TYPE II-VU
☐ TYPE II-VV
☐ TYPE II-VW
☐ TYPE II-VX
☐ TYPE II-VY
☐ TYPE II-VZ
☐ TYPE II-WA
☐ TYPE II-WB
☐ TYPE II-WC
☐ TYPE II-WD
☐ TYPE II-WE
☐ TYPE II-WF
☐ TYPE II-WG
☐ TYPE II-WH
☐ TYPE II-WI
☐ TYPE II-WJ
☐ TYPE II-WL
☐ TYPE II-WM
☐ TYPE II-WN
☐ TYPE II-WO
☐ TYPE II-WP
☐ TYPE II-WQ
☐ TYPE II-WR
☐ TYPE II-WS
☐ TYPE II-WT
☐ TYPE II-WU
☐ TYPE II-WV
☐ TYPE II-WW
☐ TYPE II-WX
☐ TYPE II-WY
☐ TYPE II-WZ
☐ TYPE II-XA
☐ TYPE II-XB
☐ TYPE II-XC
☐ TYPE II-XD
☐ TYPE II-XE
☐ TYPE II-XF
☐ TYPE II-XG
☐ TYPE II-XH
☐ TYPE II-XI
☐ TYPE II-XJ
☐ TYPE II-XL
☐ TYPE II-XM
☐ TYPE II-XN
☐ TYPE II-XO
☐ TYPE II-XP
☐ TYPE II-XQ
☐ TYPE II-XR
☐ TYPE II-XS
☐ TYPE II-XT
☐ TYPE II-XU
☐ TYPE II-XV
☐ TYPE II-XW
☐ TYPE II-XX
☐ TYPE II-XY
☐ TYPE II-XZ
☐ TYPE II-YA
☐ TYPE II-YB
☐ TYPE II-YC
☐ TYPE II-YD
☐ TYPE II-YE
☐ TYPE II-YF
☐ TYPE II-YG
☐ TYPE II-YH
☐ TYPE II-YI
☐ TYPE II-YJ
☐ TYPE II-YL
☐ TYPE II-YM
☐ TYPE II-YN
☐ TYPE II-YO
☐ TYPE II-YP
☐ TYPE II-YQ
☐ TYPE II-YR
☐ TYPE II



DOOR BUCK DETAIL


FRAME WALL INSTALLATION TO MANUFACTURERS SPECIFICATIONS

NOTE: ADHESIVE CAULK TO BE:
"MD" DOOR & WINDOW SILICONIZED
ACRYLIC CAULK (OR EQUAL)
MEETING ASTM SPEC C-834



NOTES

- SIDE HINGE DOORS MAY UTILIZE 1" x P.T. BUCKS WITH THE DOOR FRAME INSTALLED THRU THE BUCKS TO THE MASONRY/TIE BEAM WITH TAPCONS. SEE THE MANUFACTURERS DETAILS FOR TAPCON SIZE AND SPACING. 1" BUCK SIZE AND REQUIRED INSWING AND OUTSWING DOOR FRAME SIZES.
- THE DOOR MANUFACTURERS INSTALLATION DETAILS FOR THE DESIGNED PRESSURES SHALL TAKE.



NON-BEARING INTERIOR PARTITIONS

ALL INTERIOR NON BEARING PARTITIONS SHALL BE 3 1/2" METAL STUDS 26 GA. AT 24" O.C. MAX SPACING W/ 1/2" MIN. GYPSUM DRYWALL EACH SIDE OR 2"x4" STUD GRADE LUMBER OR BETTER AT 16" O.C. WITH SINGLE TOP AND BOTTOM PLATE

DOOR & WINDOWS

ALL BEDROOMS REQUIRED AN OUTSIDE WINDOW OR DOOR OPERABLE FROM THE INSIDE WITHOUT THE USE OF TOOLS OR KEYS PROVIDING A CLEAR OPENING OF NOT LESS THAN 30" WIDTH, 24" IN HEIGHT & 5.7 SQ. FT. IN AREA. THE BOTTOM OF THE OPENING SHALL NOT BE MORE THAN 44" OFF THE FLOOR AND ON PART OF THE OPERATING MECHANISM SHALL BE PLACED HIGHER THAN 54" A.F.F.

THE OPERATING MECHANISM FOR SINGLE HUNG WINDOWS SHALL BE AT OR NEAR THE SILL. MINIMUM SINGLE HUNG EGRESS WINDOW IS 5.7 SQ. FT.

WINDOW INDICATE WITH (E) MUST BE MANUFACTURE TO CONFORM TO THE BLDG. CODE W/RESPECT TO MIN. EMERGENCY EGRESS REQUIREMENTS PER N.F.P.A. 101 CHAPTER 22-2.

BATHROOMS

BATHROOM FLOOR AND BASE SHALL BE IMPERVIOUS MATERIALS. TILE FINISH SELECTED BY OWNER.

MIRRORS

MIRRORS SHALL BE ANCHORED TO STUDS WHEN IN EXCESS OF 9 S.F.

STRUCTURAL NOTES: MASONRY:

HOLLOW CONCRETE MASONRY DESIGN & CONSTRUCTION SHALL CONFORM TO THE SPECIFICATIONS OF THE NATIONAL CONCRETE MASONRY ASSOCIATION AND ACI 530.

MORTAR USED TO BOND C.M.U. SHALL CONFORM TO ASTM C 476, TYPE "M" OR "S" WITH A 28 DAY STRENGTH OF 2500 PSI.

LAY ALL MASONRY WITH FULL FACE HEAD JOINTS AND WITH FACE SHELL MORTAR BEDDING MORTAR JOISTS TO BE 3/8" +/- 1/8" MAXIMUM.

COMPRESSIVE STRENGTH OF CMU SHALL BE ON LESS THAN FM-1350 PSI. VERTICAL CELLS FOR MASONRY SHALL HAVE VERTICAL ALIGNMENT SUFFICIENT TO MAINTAIN A CLEAR, UNOBSTRUCTED CONTINUOUS CELL.

CLEAN OUT OPENINGS SHALL BE PROVIDED AT THE BOTTOM OF GROUTED CELLS AT EACH LIFT. CLEAN OUTS SHALL BE SEALED AFTER CLEANING & INSPECTION AND BEFORE GROUTING. CLEAN OUT TO FREE OF ALL DEBRIS AND MORTAR SLAG.



PRE CAST/ PRE STRESSED LINTEL SUPPLIED BY APPROVED MANUFACTURERS

1. FCP/CAST-CRETE CORPORATION
2. POWER CONCRETE
3. ALLIED PRE-CAST
4. LOTT
5. QUALITY PRE-CAST

ALL REINFORCING STEEL SHALL BE GRADE 60, MEETING ASTM SPECS A-615 REINFORCING STEEL SHALL BE FREE FROM OIL, LOOSE SCALE, AND RUST.

ALL DOWELS, SLEEVES, CONDUIT, INSERT, BLOCK OUT, ANCHORS BOLTS AND DRAINS SHALL BE IN PLACE BEFORE CONCRETING. FOR OPENING & SPECIAL FEATURES OMITTED ON THESE PLANS, SEE ARCHITECTURAL & MECHANICAL DRAWINGS.

LAP SPLICE SHALL BE AS FOLLOWS: 5 BAR 30", 4 BAR 24", 3 BAR 18".




HEAD (DOOR)


SCALE: N.T.S.

JAMB (DOOR)

SCALE: N.T.S.






SILVESTRE MARCHAN L.
CIVIL ENGINEER
C.E.O.
SERVICES AND INVESTMENT OTIM LLC








PROJECT: MODEL SAPPHIRE
OWNER: 14688 SW 24TH PL, OCALA FL 34481
JOB SITE ADDRESS:


A-04
of 07



- NOTE: ALL WOOD RAFTER TO BE FASTENED TO TIE
BEAM WITH SIMPSON HETA 20 (TYP.)
- 2X12 WOOD RAFTERS AT 16" O.C.
- (A) 2X12 WOOD RIDGE BEAM (FASTENED ALL WOOD RAFTERS TO RIDGE BEAM WITH SIMPSON LSTA30 STRAP)
- (B) 2X12 WOOD HIP (FASTENED ALL WOOD RAFTERS TO 2X12 HIP WITH SIMPSON LSSU28 - TYP.)
- (C) 2X12 WOOD VALLEY (FASTENED ALL WOOD RAFTERS TO 2X12 VALLEY WITH SIMPSON LSSU28 - TYP.)

LINTEL SCHEDULE			
TYPE	QUANTITY	CLEAR SPAN	LENGTH
L-1	05	3'-2"	4'-6"
L-2	01	6'-3.5"	7'-7.5"
L-3	02	2'-8"	4'-0"
L-4	01	3'-0"	4'-4"
L-5	01	8'-0"	9'-4"
L-6	01	6'-2"	7'-6"






FLOOR PLAN
SCALE: 1/4"=1'-0"

Note:
THE INSTALLATION OF CEILING
FANS WILL NOT BE CONSIDERED
UNLESS REQUESTED BY THE
BUYER OR THE NEW OWNER.

ELECTRICAL NOTES:

- THESE PLANS WERE PREPARED AND SHALL COMPLY W/2020 NATIONAL ELECTRICAL CODE (NEC 2020) CONTRACTOR SHALL BE RESPONSIBLE TO VERIFY THAT THE WORK OF ALL TRADES AND SHALL COMPLY WITH THE 2020 FLORIDA BUILDING CODE AND LOCAL BUILDING CODES.
- CONTRACTOR IS TO COORDINATE THE WORK OF ALL OTHER CONTRACTORS AND TRADES, WETHER HIS OWN OR THOSE OF ANY SEPERATE CONTRACTS LET BY OWNER
- CONTRACTOR SHALL VERIFY WITH OWNER ANY ADDITIONAL ELECTRICAL LIGHTING FIXTURES, FANS, SWITCHES, FLOOD LTS, ETC. -AND PROVIDE NECESSARY ELECTRICAL COMPONETS FOR PROPER INSTALLATION
- ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER BALANCE OF LOADS PER PHASE
- ALL ELECTRICAL TO BE ABOVE REQUIREMENT FLOOD ELEVATION
- ALL ELECTRICAL OUTLETS IN THE KITCHEN AND BATHROOM SHALL BE GROUND FAULT CIRCUIT-INTERRUPTER TYPE. GFI RECEPTACLES REQUIRED NEC 2020 ARTICLE 210/8
- SMOKE ALARMS TO COMPLY WITH 2020 F.B.C. RESIDENTIAL CODE, SECTION: R314 CARBON MONOXIDE ALARMS TO COMPLY WITH 2020 F.B.C. RESIDENTIAL CODE SECTION: R315
- KEEP ALL SMOKE DETECTORS MINIMUM OF 36" FROM BATHROOM DOORS AND AC OUTLETS
- IN NEW CONSTRUCTION, SMOKE DETECTORS SHALL BE HARDWIRED INTO AN AC ELECTRICAL POWER SOURCE AND SHALL BE EQUIPPED WITH A MONITORED BATTERY BACKUP
- CARBON MONOXIDE DETECTORS TO COMPLY WITH 2020 FBC, SECTION 905.2 AND ANSUL 2034-96 OR UL 2075-04.
- CEILING FANS TO BE INSTALLED IN ALL HABITABLE AREAS BEFORE FINAL INSPECTION AND C.O. PER ENERGY CALC. CREDIT
- ARC-FAULT CIRCUIT INTERRUPTER(S) REQUIRED IN DWELLING UNIT BEDROOMS PER NEC 210-12 8b/9
- ELECTRICAL CONTRACTOR SHALL INSTALL A TYPEWRITTEN SCHEDULE FOR ELECTRICAL PANEL INDICATING WHAT FACH BREAKER CONTROLS. THE DIRECTORY SHALL BE MOUNTED ON THE INNER SIDE OF THE ELECTRICAL PANEL
- DEVICES HEIGHTS:
 - ELECTRICAL OUTLET HEIGHTS AS MEASURED FROM FIN. FLR. ELEV. TO CENTERED LINE OF THE BOX TO BE 12" AFF (GENERAL)
OTHERS OUTLET HEIGHT (UNLESS OTHERWISE NOTED):
KITCHEN OUTLETS (GFI): 46" AFF
BATHROOMS OUTLETS (GFI): 46" AFF
LAUNDRY OUTLETS: 36" AFF
EXTERIOR OUTLETS (WATERPROOF): 12" AFF
GARAGE GENERAL PURPOSE: 42" AFF
KITCHEN RANGE: 6" AFF
KITCHEN DISHWASHER: 6" AFF
KITCHEN MICROWAVW: 76" AFF
REFRIGERATOR: 46" AFF TV & CABLE OUTLET:60" AFF
 - ELECTRICAL SWITCHES TO BE AT 42" CENTERLINE ABOVE FIN. FLR. ELEV.
 - ALL WORK SHALL BE DONE IN STRICT ACCORDANCE WITH THE 2020 NATIONAL ELECTRICAL CODE, LATEST EDITION, BY A LICENSED ELECTRICAL CONTRACTOR WHO SHALL BE RESPONSIBLE FOR THE INSTALLATION AND SIZING OF ALL ELECTRICAL WIRING AND ACCESSORIES
- PROVIDE LIGHT AND RECEPTACLE IN ATTIC WITH SWITCH AT ATTIC ACCESS DOOR
- GROUNDING SYSTEMS AS REQUIRED BY NEC 2020, ARTICLE 250-80 SHALL BE PROVED PRIOR TO FLOOR, FOUNDATION, OR FOOTING INSPECTION.
- ELECTRICAL CONTRACTOR SHALL MAKE FINAL CONNECTIONS ON ALL EQUIPMENT (VENTILATION, AHVC, EXHAUST FANS AND OTHER EQUIPMENT) AND/OR APPLIANCES



ELECTRICAL RISER
SCALE: N.T.S.

ELECTRICAL NOTES:

- THESE PLANS WERE PREPARED AND SHALL COMPLY W/2020 NATIONAL ELECTRICAL CODE (NEC 2020) CONTRACTOR SHALL BE RESPONSIBLE TO VERIFY THAT THE WORK OF ALL TRADES AND SHALL COMPLY WITH THE 2020 FLORIDA BUILDING CODE AND LOCAL BUILDING CODES.
- CONTRACTOR IS TO COORDINATE THE WORK OF ALL OTHER CONTRACTORS AND TRADES, WETHER HIS OWN OR THOSE OF ANY SEPERATE CONTRACTS LET BY OWNER
- CONTRACTOR SHALL VERIFY WITH OWNER ANY ADDITIONAL ELECTRICAL LIGHTING FIXTURES, FANS, SWITCHES, FLOOD LTS, ETC. -AND PROVIDE NECESSARY ELECTRICAL COMPONENTS FOR PROPER INSTALLATION
- ALL ELECTRICAL TO BE ABOVE REQUIREMENT FLOOD ELEVATION
- ARC-FAULT CIRCUIT INTERRUPTER(S) REQUIRED IN DWELLING UNIT BEDROOMS PER NEC 210-12(b)
- ALL ELECTRICAL OUTLETS IN THE KITCHEN AND BATHROOM SHALL BE GROUND FAULT CIRCUIT-INTERRUPTER TYPE. GFI RECEPTACLES REQUIRED NEC 2020 ARTICLE 210/8
- ALL BRANCH CIRCUITS THAT SUPPLY 125 VOLT SINGLE PHASE, 15 AND 20 AMPERES
- RETAIN AND UTILIZE EXISTING ELECTRICAL (OUTLETS, SWITCHES, FIXTURES ETC.) WHERE FEASIBLE!

IMPORTANT NOTE:

- PRIOR FINAL INSPECTION, ALL NEWS AND MODIFIED BRANCH CIRCUITS SHALL BE IDENTIFIED AS TO PURPOSE OR USE AT THE COPRESPONDING PANEL BOARD DIRECTORY, COMPLY WITH COMPLY WITH 2020 NEC, SECTION 408.4

LOAD CALCULATION

GENERAL LIGHTING AND RECEPTACLES			
3 WATTS PER SQUARE FEET OF LIVING			
LIVING AREA =	AREA X POWER UNIT		
1,171.70	X	3.00	3,515.10 (a)
APPLIANCE CIRCUITS:			
RANGE / OVEN:		8,000.00	
MICRO / HOOD:		1,000.00	
WATER HEATHER:		4,500.00	
REFRIGERATOR:		1,250.00	
WASHER		1,500.00	
DRYER:		5,000.00	
DISHWASHER:		1,500.00	
DISPOSAL:		600.00	
SMALL APPLIANCE CIRCUITS (03):		4,500.00	
BATH FAN (100 PER EACH):		700.00	
APP. CIR. TOTAL:		28,550.00	(b)

GEN. LIGHTING & RECEP. + APP.CIR.TOTAL:	(a) + (b) =
	32,065.10
SUBTRACT 100% OF FIRST 10,000	- 10,000.00
	(A) 22,065.10

HVCA CIRCUITS:	
A/C (AIR HANDLER & COMP):	10,000.00
A/C (AUXILIAR HEAT STRIP):	10,000.00
	(B) 20,000.00

CIRCUITS CALCULATIONS:	
FIRST 10,000 AMPS @ 100%	= 10,000.00
+ 40% OF "A" = (0.40 x 24,550)	= 8,826.04
+ 100% OF "B" = (20,000)	= 20,000.00
TOTAL WATTAGE	38,826.04

WATTS DIVIDED BY 240 = AMPS	
CALCULATE SERVICES AMPS	= 161.78

OWNER SELECTED: 200 AMPS ELECTRICAL PANEL


ELECTRICAL SYMBOLS

NOTE: Electrical symbol's for illustration only.
Contractor/or Owner to verify final model's and design's

	SMOKE DETECTOR w/CO2 Carbon Monoxide Alarm (Electric powered w/Batteries back-up)		PRE-WIRE CHANDELER		FLAT SURFACE (Soffit Light)		110V 1/2 LIVE DUPLEX RECEPTACLE		E.O.S. EMERGENCY
	BATH LIGHT w/EXHAUST FAN RECESS		PRE-WIRE CHANDELER		CABLE T.V.		110V GROUND-FAULT CIRCUIT-INTERRUPTER w/COVER PROTECTOR		ELECTRICAL PANEL DIS-CONNECT SERVICE
	EXHAUST FAN		SUSPENDED CLG. LIGHT		SECURITY CAMERA (Pre-wire electrical and Cctv cable)		220V		Electrical Meter
	LIGHT FIXTURE (Flat Surface Contractor to Verify)		PRE-WIRE CLG. FAN w/LIGHT (Split Switch-off)		DOOR BELL		FLOOR RECEPTACLE (Contractor to Verify Location)		FIRE ALARM
	4" LIGHT FIXTURE (Flat Surface Contractor to Verify)		WALL MOUNTED LIGHT's		DOOR BELL CHIMES		OUTLET @ SOFFIT AREA (Contractor to Verify Location)		EXHAUST FAN
	WALL MOUNTED EXTERIOR LIGHT FIXTURE		FLAT SURFACE LED LIGHT		PUSH BUTTON DOOR OPENER		LIGHT SWITCH		120V. GFI RECEPTACLE @CEILING
	CEILING LIGHT FIXTURE		MOTION SENSOR LIGHT		110V DUPLEX RECEPTACLE		3 WAY SWITCH		Electrical Meter
	ATTIC LIGHT FIXTURE		EXTERIOR CEILING LIGHT FIXTURE		110V GROUND-FAULT CIRCUIT-INTERRUPTER		SINGLE POLE DIMMER SWITCH		








SILVESTRE MARCHAN L.
CIVIL ENGINEER
C.E.O.
SERVICES AND INVESTMET OTIM LLC





PROJECT: MODEL SAPPHIRE


E-01
of 07



- LEGEND**
- 1 A. PLYWOOD WITH STEEL NAIL 2 1/2 @ 60"
B. LAMINATED PLASTIC COVER
C. ASPHALT SHINGLE:
SHINGLE TYPE: APP/SBS ON #30 FELT COVERING ON WOODEN BEAMS. MUST BE ATTACHED TO ROOF FRAME WITH 8D RING SHAFI NAIL AT 6" ON CENTER AT EDGE AND 6" ON CENTER IN INTERMEDIATE FRAMING.
 - 2 2x4 X 4'-0" LONG MIN. WOOD OVERHANG BLOOMING FASTENED TO FACE OF RAFTER WITH 10d NAILS AT 4' O.C.
 - 3 26 ga. GALVANIZED METAL OR 0.019 PAINTABLE ALUMINUM DRIP
 - 4 1x3 R.S. DRIP
 - 5 2x6 R.S. CEDAR FASOIA OR VINYL
 - 6 2x4 WOOD BLOOMING
 - 7 VENTILATED SOFFIT
 - 8 BOND BEAM (SEE STRUCTURAL DWGS.)
 - 9 1/2" PARCE COAT CEMENTITIOUS FINISH-TWO COATS WITH FINISH SELECTED BY OWNER OVER 8" CMU BLOCK AND BEAM
 - 10 VERTICAL REINFORCING REBAR (SEE STRUCTURAL DRAWINGS FOR SIZE AND ARCH. DWGS FOR LOCATIONS)
 - 11 NOT USED
 - 12 APPROXIMATE FINISHED GRADE
 - 13 CONCRETE FOOTING (SEE STRUCTURAL DRAWINGS) OPTIONAL STEM WALL FOOTING
 - 14 R30 BATT INSULATION
 - 15 1/2" GYPSUM CEILING BOARD (SAG RESISTANT)
 - 16 1x2 OR 1x3 FURRING STRIPS AT 16" O.C. (TYPICAL)
 - 17 TRUSS ANCHORING SYSTEM (SEE STRUCTURAL DRAWINGS FOR MODEL AND MANUFACTURER)
 - 18 R4.1 FOIL INSULATION
 - 19 1/2" GYPSUM WALLBOARD-PANELS APPLIED VERTICALLY OR HORIZONTALLY
 - 20 40 DIAMETER BAR EXTENSION (SEE ARCH. DWGS. FOR LOCATIONS)
 - 21 BASE BOARD (MODEL SELECTED BY OWNER OR CONTRACTOR)
 - 22 1x2 OR 1x3 P.T. WOOD BOTTOM FURRING STRIPS (TYPICAL)
 - 23 FINISHED FLOORING (SEE ARCH. DWG. FINISH SCHEDULE)
 - 24 4" CONCRETE SLAB (3,000 MIN. PSI AT 28 DAYS, ON GRADE WITH 6x6-W/4" x W/4" W.W.F. ON 6 MIL. PLASTIC VAPOR BARRIER WITH 6" OVERLAP JOINTS ON TERMITE TREAT AND CLEAN SOIL (TYP.) SEE STRUCTURAL DRAWINGS FOR SOIL COMPACTION




SILVESTRE MARCHAN L.
CIVIL ENGINEER
C.E.O.
SERVICES AND INVESTMENT OTIM LLC




PROJECT: MODEL SAPPHIRE
OWNER: X
JOB SITE ADDRESS: 14689 SW 24TH PL, OCALA FL 34481

A-01
of 07

TYP. MASONRY WALL CONSTRUCTION
SCALE: N.T.S.




CONTINUITY OF VERTICAL REINFORCEMENT
SCALE: N.T.S.




NOTE: THE CONTRACTOR IS CAUTIONED THAT THE PRECISION SETTING OF WET SET ANCHORS IN THE BEAM IS REQUIRED CONSULT THE TRUSS PLACEMENT PLANS, THE ARCHITECTURAL PLANS DETAILS FOR SPECIFIC REQUIREMENTS.

GARAGE DOOR BUCK DETAIL
DOOR INSTALLATION PER MANUFACTURER SPECIFICATIONS
SCALE: N.T.S.




DOOR BUCK DETAIL
DOOR INSTALLATION PER MANUFACTURER SPECIFICATIONS
SCALE: N.T.S.




CAST-IN-PLACE CONCRETE REINFORCING BAR LAP SPLICE
SCHEDULE
SCALE: N.T.S.

BAR SIZE F _y =60 ksi	TENSION BARS			COMPRESSION BARS			BAR SIZE F _y =60 ksi	TENSION BARS			COMPRESSION BARS		
	3000 PSI	4000 PSI	5000 PSI	ALL STRENGTHS	15"	19"		3000 PSI	4000 PSI	5000 PSI	ALL STRENGTHS	15"	19"
#4	29"	25"	22"	15"	19"	23"	#4	29"	25"	22"	15"	19"	23"
#5	36"	31"	28"	15"	19"	23"	#5	36"	31"	28"	15"	19"	23"
#6	43"	37"	33"	15"	19"	23"	#6	43"	37"	33"	15"	19"	23"
#7	51"	44"	39"	15"	19"	23"	#7	51"	44"	39"	15"	19"	23"
#8	59"	51"	45"	15"	19"	23"	#8	59"	51"	45"	15"	19"	23"
#9	67"	58"	51"	15"	19"	23"	#9	67"	58"	51"	15"	19"	23"
#10	75"	65"	58"	15"	19"	23"	#10	75"	65"	58"	15"	19"	23"
#11	83"	72"	64"	15"	19"	23"	#11	83"	72"	64"	15"	19"	23"




FRAME BRG. WALL DETAIL
SCALE: N.T.S.




NOTE: 1. BEARING WALL DESIGNED FOR GRAVITY LOAD OF #500 AND AN UPLIFT LOAD OF #1000. 2. REFER TO FLOOR PLAN OR FRAMING MATERIAL, SIZE AND SPACING. 3. FASTEN BEAMS AND STUDS W/ 16" NAILS AT 16" O.C. 4. SPACE FRAMING FROM HEADER TO TOP OF WINDOW/DOOR OPENING IF NECESSARY. 5. EQUIVALENT FASTENERS OF OTHER MANUFACTURERS MAY BE SUBSTITUTED FOR THE LISTED FASTENERS.

FRAME WALL (non-brg.) DETAIL
SCALE: N.T.S.




MASONRY WINDOW ATTACHMENT
SCALE: N.T.S.



HEADER BEAM SCHEDULE (BEARING)

SPAN	HEADER BEAM DESCRIPTION	HEADER STUDS
0 TO 8'-0"	(multi-ply = wall thickness) 2x10s w/ 1/2" PLYWOOD SPACERS AS REQUIRED	2
Above 8'-0"	(multi-ply = wall thickness) 2x12s w/ 1/2" PLYWOOD SPACERS AS REQUIRED	3
Above 12'-0"	(multi-ply = wall thickness) 1 1/2" x 11 1/2" GEORGIA PACIFIC 2.0m LVL	3



MINIMUM DESIGN WIND PRESSURE (PSF)

ZONE	10 FT	20 FT	50 FT	100 FT	500 FT
INTERIOR	+26.5/-42.1	+24.2/-41.0	+21.1/-38.4	+18.7/-36.2	+18.7/-35.2
EDGE	+26.5/-73.4	+24.2/-67.5	+21.1/-58.7	+18.7/-53.8	+18.7/-53.9
OVERHANG	-85.9	-85.9	-85.9	-85.9	-85.9
CORNER	+26.5/-108.5	+24.2/-101.4	+21.1/-92.1	+18.7/-85.1	+18.7/-85.1
OVERHANG	-144.4	-130.3	-111.7	-97.6	-97.6
INTERIOR	+48.1/-50.0	+44.0/-47.9	+41.2/-45.1	+39.2/-43.1	+34.3/-38.2
CORNER	+48.1/-61.7	+44.0/-57.5	+41.2/-52.0	+39.2/-47.9	+34.3/-38.2

ROOF SHEATHING CONNECTORS

ANCHOR DIAMETER (IN)	MIN. EMBEDMENT (IN)	CRITICAL EDGE DISTANCE (IN)	CRITICAL SPACING (IN)	ALLOWABLE TENSION (LBS)	ALLOWABLE SHEAR (LBS)	INSTALL TORQUE (FT-LBS)
1/4	1-1/8	2-1/2	2-1/2	205	230	8
3/8	2-1/4	2-1/2	3-1/8	530	230	30
1/2	3-1/4	3-3/4	2-3/8	555	570	60
5/8	4-1/4	3-3/4	3-5/8	1,100	1,055	90
3/4	5-1/4	3-3/4	4-3/4	1,140	1,055	150
1	6-1/4	3-3/4	5-1/8	1,070	1,485	300

SIMPSON STRONG-TIE WEDGE-ALL SPECIFICATION

ANCHOR DIAMETER (IN)	MIN. EMBEDMENT (IN)	CRITICAL EDGE DISTANCE (IN)	CRITICAL SPACING (IN)	ALLOWABLE TENSION (LBS)	ALLOWABLE SHEAR (LBS)	INSTALL TORQUE (FT-LBS)
1/4	1-1/8	2-1/2	2-1/2	205	230	8
3/8	2-1/4	2-1/2	3-1/8	530	230	30
1/2	3-1/4	3-3/4	2-3/8	555	570	60
5/8	4-1/4	3-3/4	3-5/8	1,100	1,055	90
3/4	5-1/4	3-3/4	4-3/4	1,140	1,055	150
1	6-1/4	3-3/4	5-1/8	1,070	1,485	300

NOTES:

- 1.-Allowable loads listed are based on a safety factor of 4.
- 2.-Allowable loads are based on f'c = 3000 psi.
- 3.-Minimum concrete thickness is 1.5 times embedment depth.
- 4.-Refer to Simpson Strong-Tie Wedge-All specification for further information.
- 5.-All fasteners are to be Carbon Steel.
- 6.-Provide Zinc Plated fasteners for interior applications.
- 7.-Provide Hot-Dipped Galvanized for exterior applications.
- 8.-Florida Product Approval # FL11506.8 for all Simpson Strong-Tie Wedge-All Products listed above.

MINIMUM FASTENING REQUIREMENTS FOR MULTI-PLY LVL BEAMS

Fastener Type	LVL Depth	3-1/2" Wide		5-1/4" Wide		7" Wide	
		2-ply	3-ply	2-ply	3-ply	2-ply	3-ply
10d Nails	7-1/4" ≤ d ≤ 14"	3 rows @ 12" o.c.	3 rows @ 12" o.c. (ES)	4 rows @ 12" o.c. (ES)	4 rows @ 12" o.c. (ES)	4 rows @ 12" o.c. (ES)	4 rows @ 12" o.c. (ES)
16d Nails	7-1/4" ≤ d ≤ 14"	2 rows @ 12" o.c.	2 rows @ 12" o.c. (ES)	3 rows @ 12" o.c. (ES)	3 rows @ 12" o.c. (ES)	3 rows @ 12" o.c. (ES)	3 rows @ 12" o.c. (ES)
1/2" Thru-Bolts	d ≥ 7 1/2"	2 rows @ 24" o.c.	2 rows @ 24" o.c. (ES)	2 rows @ 18" o.c. (ES)	2 rows @ 24" o.c. (ES)	2 rows @ 24" o.c. (ES)	2 rows @ 24" o.c. (ES)
SDS 1/4" x 3-1/2" SDS 1/4" x 6" 5" TrusLok 6" TrusLok	d ≥ 7 1/2"	2 rows @ 24" o.c.	2 rows @ 24" o.c. (ES)	2 rows @ 24" o.c. (ES)	2 rows @ 24" o.c. (ES)	2 rows @ 24" o.c. (ES)	2 rows @ 24" o.c. (ES)

1.- (ES) = Each Side, offset fasteners up to 1/2" of the on center spacing. 2.- Consult Georgia Pacific Specification Manual for Additional Information. 3.- Fastener spacing based on the 2005 NDS Manual.

FASTENER CLEARANCES FOR MULTI-PLY MEMBERS


Fastener Type	A	B	C	D
10d & 16d Nails	MIN. 2"	MIN. 4"	MIN. 4"	MIN. 3"
Bolts & Screws	2"	4"	4"	3"

CONCRETE ANCHOR SPECIFICATIONS


FASTENER	Min. Embedment	Allowable Shear Load	Allowable Tension Load	Material	Substrate Material	Fla. Product Approval
3/16" @ TITEN Screw	1-1/4"	220#	160#	Carbon Steel	Hollow or Grout Filled CMU	2355.1
3/16" @ TITEN Screw	1-1/4"	250#	305#	Carbon Steel	Concrete	2355.1
3/16" @ TITEN Screw	1-1/4"	78#	78#	Stainless Steel	Hollow or Grout Filled CMU	2355.1
1/4" @ TITEN Screw	1-1/4"	300#	165#	Carbon Steel	Hollow or Grout Filled CMU	2355.1
1/4" @ TITEN Screw	1-1/4"	400#	365#	Carbon Steel	Concrete	2355.1
1/4" @ TITEN Screw	1-1/4"	124#	137#	Stainless Steel	Hollow or Grout Filled CMU	2355.1
1/2" @ TITEN HD Screw	2-3/4"	870#	680#	Carbon Steel	Grouted CMU	11506.7
1/2" @ TITEN HD Screw	3-1/2"	1,385#	690#	Carbon Steel	Grouted CMU	11506.7
5/8" @ TITEN HD Screw	4-1/2"	2,085#	1,060#	Carbon Steel	Grouted CMU	11506.7
3/4" @ TITEN HD Screw	5-1/2"	3,000#	1,600#	Carbon Steel	Grouted CMU	11506.7

Notes: 1.- Stainless steel fasteners may only be used when specifically stated on the detail drawings. 2.- Design values in masonry substrate refer to face shell embedment only. 3.- Simpson fasteners may not be installed within 1-1/4" of mortar joint, when installed into masonry. 4.- All fasteners design values into concrete substrate are based on 3,000 psi concrete strength.


CORNER BEAM




DOOR HEAD DETAIL




CORNER FOOTING




WINDOW JAMB DETAIL



GARAGE DOOR JAMB DETAIL



SILVESTRE MARCHAN L.
CIVIL ENGINEER
C.E.O.
SERVICES AND INVESTMENT OTIM LLC



PROJECT: MODEL SAPPHIRE
OWNER: 14688 SW 24TH PL, OCALA FL 34481
JOB SITE ADDRESS: 14688 SW 24TH PL, OCALA FL 34481

A-05
of 07