

ADVERTISEMENT FOR BIDS

Notice is hereby given that sealed bids will be received by the Bartow Airport Authority, 5993 Airport Blvd., Bartow, Florida 33830, until **October 20, 2026, at 2:00 PM** for the following:

BUILDINGS 425 AND 425A ROOF REPLACEMENT

Project Description. The project generally consists of furnishing all labor, supervision, equipment, materials, permits, disposal, and incidentals necessary to remove and replace the existing metal roofing systems on Buildings 425 and 425A at Bartow Executive Airport, together with associated trim, flashing, insulation, and related roof components as described in the attached specifications.

All bids must be submitted in a sealed envelope plainly marked on the outside: **“SEALED BID – BUILDINGS 425 AND 425A ROOF REPLACEMENT”** and delivered to the office of the Executive Director, Bartow Airport Authority, 5993 Airport Blvd., Bartow, Florida 33830, no later than the date and time specified above. Late bids will not be considered.

The Bartow Airport Authority reserves the right to accept or reject any or all bids or any part thereof, to waive informalities or irregularities, and to make an award in the best interest of the Authority.

Questions regarding this solicitation shall be directed to: Terry Beacham, Deputy Executive Director, at (863) 533-1195 or email terry@bartow-airport.com

BARTOW AIRPORT AUTHORITY

P.O. Box 650, Bartow, Florida 33831 (mailing address)

5993 Airport Blvd., Bartow, Florida 33830 (physical address)

John Helms, Executive Director – (863) 533-1195

Advertisement Date: **September 17, 2026**

BUILDINGS 425 AND 425A ROOF REPLACEMENT

TECHNICAL SPECIFICATIONS / SCOPE OF WORK

General Scope. Provide all labor, supervision, materials, equipment, permits, disposal, and incidentals necessary to complete the roof replacement for Buildings 425 and 425A. Contractor shall field verify all roof dimensions, existing conditions, penetrations, drainage components, and quantities before submitting a bid.

- Remove and properly dispose of existing roof sheets, trim, flashing, insulation, fasteners, and other roofing materials necessary to complete the work.
- Install new 26-gauge, 12-rib metal roof panels with Galvalume finish, unless an equivalent or superior system is approved by the Authority.
- Fasten new roof panels using ZAC long-life screws or an approved equivalent fastening system compatible with the roofing manufacturer's requirements.
- Install new rake trim, ridge caps, eave trim, flashing, closures, sealants, and other accessories required for a complete, weather-tight roofing system.
- Install new 3-inch-thick, R-10 fiberglass roof insulation throughout Buildings 425 and 425A. Insulation shall have a white reinforced vinyl vapor-retarder facing exposed to the building interior and shall be installed continuously between the roof panels and structural framing in accordance with the insulation and roofing manufacturers' requirements. All seams, joints, penetrations, and damaged areas shall be securely sealed or repaired to provide a uniform finished appearance and continuous vapor barrier. Contractor shall field verify all dimensions and quantities before installation.
- Properly flash and seal all roof penetrations, vents, curbs, pipes, and other roof-mounted components. Existing components that are to remain shall be protected during construction.
- Roofing materials, fasteners, and installation shall comply with applicable Florida Building Code requirements and manufacturer requirements, including applicable wind-uplift requirements.
- Contractor shall inspect the existing roof framing and substrate exposed during removal. Any deteriorated or damaged structural components requiring repair shall be brought to the Authority's attention before additional work is performed.
- Contractor shall protect the buildings, contents, adjacent pavement, vehicles, aircraft, and Airport property from weather and construction-related damage throughout the work.
- Coordinate work with Airport staff so that Airport and tenant operations are disrupted as little as reasonably possible.
- Provide daily cleanup and remove all construction debris, loose fasteners, metal fragments, and other foreign object debris (FOD) from the work area and surrounding Airport property.
- Obtain all required permits and inspections.
- Upon completion, provide manufacturer warranty information and any contractor workmanship warranty applicable to the completed roofing system.